

## RECLAMATION & CONSTRUCTION INSPECTION PLAN

The purpose of this plan is to assure the reclamation plan is followed throughout the mining and reclamation process.

It is the operator's responsibility to notify the Land Conservation Department 2 work days in advance of when these work items will be occurring.

- Clearing & grubbing
- Topsoil stripping
- Berm / stockpile construction (A horizon, B horizon, overburden soils only)
- Storm water pond construction <sup>PE</sup>
- Storm water diversion construction <sup>PE</sup>
- A & B horizon soils reapplication
- Installation of other BMPs (erosion mat, silt fence...)
- Importing material (Any material brought into the mine to be used as fill or as soil amendments)
- Temporary storm water infiltration basin construction
- Removal of berm / stockpile

It is the operator's responsibility to notify the Land Conservation Department immediately in the event of any of the following.

- Failure of any storm water facility (pond, infiltration basin, diversion...) <sup>PE</sup>
- Spills covered in the SPCC plan

<sup>PE</sup> These items require the assistance of a private sector professional engineer.